

15-077-20155-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1974
CONSERVATION DIVISION
Wichita, Kansas
12-26-1974

Operator's Full Name J.A Allison

Complete Address Suite 748 200 W Douglas Wichita, KS

Lease Name Wethington Well No. 1

Location C NE/NW Sec. 12 Twp. 33 Rge. 6 (E) (W)

County Harper Total Depth 4844

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor F & F Well Service

Address Box 37 Towanda, KS License No. 714

Operation Completed: Hour 5:00 PM Day 23 Month 12 Year 1974

The above well was plugged as follows:

247 ft 8 5/8 surface cement circulated. 4837 ft 5 1/2 long string
cemented with 190 sacks. Top perf. 3774 ft. Sand to 3700 ft, 5
sacks cement with bailer. Pulled 2350 ft 5 1/2. Set 30 ft rock bridge
at 260 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor