

KANSAS

Form CP-3
Rev. 6-1-68 ED
STATE CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

JUL 15 1976
7-15-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,218.0000 (of this well)

Operator's Full Name Theodore I. Leben & Associates.

Complete Address 1555 E. 2nd., Wichita, Kansas

Lease Name Howard Well No. 1

Location SW NE Sec. 34 Twp. 17 Rge. (E) (W) 23

County Ness Total Depth 4465'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor DNB Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11 PP Day 13 Month 7 Year 1976

The above well was plugged as follows:

RTD 4465' 8 5/8 csg set 292' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/29/76

INV. NO. 3524-10