

15135-26784-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1974
10-24-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Jayhawk Oil Company
Complete Address 240 Sutton Place, Wichita, Kansas 67202
Lease Name Klitzke Well No. 1
Location C NE SW Sec. 30 Twp. 17 Rge. (E) (W) 23
County Ness Total Depth 4500'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering, Inc.
Address Box 698 Great Bend, Kansas License No. 670
Operation Completed: Hour 10:45 A Day 22 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 4500' 8 5/8 csg set at 284' cwc 160 sk.
5 1/2 csg set at 4496' cw 100 sx cem. & perf. (4288')
Set 5 1/2 wood plug at 4250' -poured 10' sd- Dumped 5 sk cem W/dump bailer. (4250-4200)
Cutoff & recovered A/2500' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water -70 sx poz 6% -10 sx gel & water -
released 8 5/8 plug & pumped 50 sk poz 6% W/100 lbs hulls by Allied Cementing Co.
PP 400 lbs. SIP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/24/74
INV. NO. 184-w

Signed: [Signature]
Well Plugging Supervisor