

15-007-00374-0000

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1963
7-29-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morgenstern & Spector Inc.

Complete Address: P. O. Box 661, Russell, Kansas

Lease Name Fritz Stumph-Smith Community Well No. # 1

Location C NE NW Sec. 19 Twp. 32 Rge. 14 (E) (W)W

County Barber Total Depth 4910

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 4:00PM Day 24th Month July Year 1963

The Above well was plugged as follows:

225' of 8 5/8" surface pipe, cement circulated. 4906' of 5 1/2" long string,
cemented with 200 sacks. Sanded to 4890', cemented with 5 sacks.

Hole was filled with mud to 250', 10' rock bridge, cemented with 20 sacks.

Hole filled with mud to 40', 10' rock bridge, cemented with 10 sacks
to base cellar.

3650' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/29/63

INV. NO. 7499-u