

CP3

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date 5 February, 1959, authorized the following plugging operation:

Operator's Full Name: Pickrell Drilling Co.

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kans.

Lease Name: Stump - Fritz Well No. 1

Location: NW NW NW Sec. 19 Twp. 32 Rge. 14 (E) (W) X

County: Barber Total Depth: 5033

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

200' of 13 3/8" surface casing circulated with cement.
Fill hole to 190' with heavy drilling mud. Set cementing plug
at 190' and and place 30 sack cement through drill pipe.
Heavy drilling mud to 35'. Set cementing plug and tie at
35' with cement from plug to base of cellar.

Very truly yours,

Signed: [Signature]
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
FEB 11 1959
2-11-59
CONSERVATION DIVISION
Wichita, Kansas