

Y  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 2 1964  
1-2-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Aylward Drilling Co.

Complete Address: 813 1st National Bank Bldg., Wichita, Kansas

Lease Name Stump Smith Well No. # 2

Location C NW Sec. 17 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 4703

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 342, El Dorado, Kansas License No. 547

Operation Completed: Hour 10:30AM Day 31st Month December Year 1963

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cement circulated. 4701' of 5 1/2" long string,  
cemented with 75 sacks. Top perferation 4632'. Bottom of hole was sanded  
to 4600', and cemented with 5 sacks. Hole was filled with mud to 225',  
10' rock bridge, and cemented with 25 sacks. Hole was filled with mud to  
40', 10' rock bridge, and cemented with 10 sacks to base cellar.  
4200' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 1/3/64

INV. NO. 8394-11

Signed: Archie Elving  
Well Plugging Supervisor