

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bowers Drlg. Co.

Complete Address 1434 Vickers KSB&T Bldg. Wichita, Ks

Lease Name Elsa Well No. 1

Location C SW/NW Sec. 14 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 4885

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 4:00 PM Day 31 Month 1 Year 1972

The above well was plugged as follows:

919 ft 8 5/8 surface pipe cemented with 500 sacks. 4410 ft 5 1/2 long

string cemented with 160 sacks. Plug back at 4478 ft. Top perf.

3890 ft. Sand back to 3850 ft, 5 sacks cement with bailer. Pulled

3475 ft 5 1/2. Set 10 ft rock bridge at 2700 ft. Fill hole with 4 yds

redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 2-2-72

INV. NO. 5113-W