

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-8-70
JUL 8 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Sierra Oil Co.

Complete Address 211 N. Broadway Wichita, Ks.

Lease Name Lake Well No. 1

Location NW/SW/SW Sec. 12 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 4433

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Co. Inc.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 7:30 PM Day 6 Month 7 Year 1970

The above well was plugged as follows:

858 ft of 8 5/8 surface pipe cemented with 475 sacks. 4432 ft of 5 1/2
long string cemented with 150 sacks. Top perf. 4101 ft. Sand back
to 4075, 5 sacks cement with bailer. Pulled 3539 ft of 5 1/2. Set plug,
10 ft rock bridge at 360 ft. Fill with redimix to base of cellar.
This well was replugged because of a leak. Replug was successful.

I hereby certify that the above well was plugged as herein stated.

Signed: J. Russell Bikerstein
Well Plugging Supervisor