

15 007- 1975-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*14*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
6-18-70  
JUN 18 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Sierra Oil Co.

Complete Address 211 N. Broadway Wichita, Ks

Lease Name Lake Well No. 1

Location NW/SW/SW Sec. 12 Twp 32 Rge. 14 (E) (W) W

County Barber Total Depth 4433

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling Co. Inc.

Address Box 364 Great Bend, Ks License No. 399

Operation Completed: Hour 6:00PM Day 16 Month 6 Year 1970

The above well was plugged as follows:  
858 ft of 8 5/8 surface pipe cemented with 475 sacks. 4432 ft of 5 1/2  
long string cemented with 150 sacks. Top perf. 4101 ft. Sand back  
to 4075, 5 sacks cement with bailer. Pulled 3539 ft of 5 1/2. ~~and~~  
~~back to 4075 ft, 5 sacks wt cement with bailer.~~ Bottom plug at 500  
ft, 10 ft rock bridge, 25 sacks cement. Mud to 40 ft, 10 ft rock  
bridge, 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. Russell Brunton*  
Well Plugging Supervisor

DATE 6/18/70  
INV. NO. 2091-W