

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 1 - 1964  
10-1-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Mull Drilling Company Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Barkley Well No. # 1

Location SE NE NE Sec. 10 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 4927

Abandoned Oil Well      Gas Well   X   Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 1:30PM Day 30th Month Sept. Year 1964

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cemented with 135 sacks. 4927' of 5 1/2" long  
string, cemented with 150 sacks. Plug back to 4210'. Top perforation  
4153'. Bottom of the hole was sanded to 4140', and cemented with 5  
sacks. Fluid in the hole was bailed down to 200'. Bridge plug was set  
on fluid at 200', and 10' of rock bridge, and cemented with 25 sacks.  
Hole was filled with mud to 40', and 10' of rock bridge, and cemented  
with 10 sacks to the base of the cellar.

3550' of 5 1/2" long string was recovered from the hole.

I hereby certify that ~~the~~ **W O C I E D** above well was plugged as herein stated.

DATE 10/1/64  
INV. NO. 9904-W

Signed: Archie Elving  
Well Plugging Supervisor