

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1978
5-26-78

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-007-00041-0000 (of this well)

Operator's Full Name Byrdward, Dalby Co.
Complete Address 909-1st Nat. Bank Bldg, Wichita, Kans. - 67202
Lease Name Barkley Well No. 2
Location NE-SW-SW Sec. 9 Twp. 32^S Rge. 14 (E) (W) X
County Barber Total Depth 4887
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____
Plugging Contractor Felsa Casing Pulling
Address Box 176 Chase, Kans. - 67524 License No. 683
Operation Completed: Hour 1:45 pm Day 22 Month May Year 1978

The above well was plugged as follows:
227' 8 5/8" Casing w/ 225 sac Cement - 5 1/2" Casing set @ 4149'
w/ 75 sac Cement prep. 4052' - 82' Sand back to 4200'
topped w/ 5 sac mixed Cement w/ dump bailer - full 36.53'
5 1/2" Casing mixed & pumped 15 Gel. 5 shells - 10 Gel. release
plug - mixed & pumped 125 sac 50/50 pre-mix Cement to
top of casing - shut in w/ 200^{psi} pump pressure -
pumped by
Allied Cementing Co - Alt Bond, Kans - 67530

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6-1-78
INV. NO. 7379-4