

*MP*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 30 1964

9-30-64

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Quality Supply Company

Complete Address: 6320 Jacqueline, Wichita, Kansas

Lease Name Miles "C" Well No. # 1

Location NW/4 Sec. 9 Twp. 32 Rge. 14 (E) (W)W

County Barber Total Depth 4140

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 11:30AM Day 29th Month Sept. Year 1964

The Above well was plugged as follows:

160' of 13 3/8" surface pipe, cement circulated. 4140' of 4 1/2" long  
string, cemented with 100 sacks. Top perforation 4063'. Bottom of the  
hole was sanded to 4040', and cemented with 3 sacks. Hole was filled  
with mud to 250', and 20' of rock bridge, and cemented with 70 sacks,  
bringing the top of the cement to 150' in the surface pipe. Hole was  
filled with mud to 40', and 10' of rock bridge, and cemented with 25  
sacks to the base of the cellar.

3553' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving  
Well Plugging Supervisor

DATE 9/30/64

INV. NO. 9902-4