

14

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1966
11-2-66
CITY OF WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address: P. O. Box 169, Russell, Kansas

Lease Name Stump-Smith Well No. # 1

Location NE SW SW Sec. 7 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 4970'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Company

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 2:00PM Day 31st Month Oct. Year 1966

The Above well was plugged as follows:

400' of 10 3/4" surface pipe, cement circulated. 4963' of 7" long
string, cemented with 200 sacks. This is an open hole. Bottom of the
hole was sanded to 4950', and cemented with 6 sacks. 3788' of 7" long
string was recovered from the hole. Fluid level in the hole was at
300', bridge plug and rock bridge from 300' to 290', and cemented
with 30 sacks. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/2/66

INV. NO. 4222-u