

KANSAS

Form CP-3  
Rev. 6-4-68

R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
CORPORATION COMMISSION  
NOV 12 1976  
11-12-76  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -007 -00029-00-01 (of this well)

Operator's Full Name National Development

Complete Address 404 Wetmore Drive Wichita, KS

Lease Name Mills Well No. 1

Location C S/2 S/2 SE Sec. 5 Twp. 32 Rge. 14 (E) (W)W

County Barber Total Depth 4986

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Co

Address Box 176 Chase, KS License No. 683

Operation Completed: Hour 5:00 PM Day 10 Month 11 Year 1976

The above well was plugged as follows:

250 ft 13 3/8 surface cement circulated. 4910 ft 5 1/2 long string  
cemented with 200 sacks. Top perf. 4382 ft. Sand to 4300 ft, 5  
sacks cement with bailer. Pulled 3615 ft 5 1/2. Set 10 ft rock bridge  
at 250 ft. Fill hole with 9 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Musell Bikerstein  
Well Plugging Supervisor

**INVOICED**

DATE 11-15-76

INV. NO. 4144-W