

KANSAS

SL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
2-2-72
FEB 2 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bowers Drlg. Co.

Complete Address 1434 Vickers KSB&T Bldg. Wichita, Ks

Lease Name Lake Well No. 2

Location C SE/SW/SW Sec. 1 Twp. 32 Rge. 14 (E) (W) W

County Barber Total Depth 3828

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co. Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 5:00 PM Day 31 Month 1 Year 1972

The above well was plugged as follows:

254 ft 8 5/8 surface pipe cemented with 200 sacks. 3820 ft 4 1/2 long
string cemented with 100 sacks. Top perf. 3504 ft. Sand back to
3475 ft, 4 sacks cement with bailer. Pulled 3145 ft 4 1/2. Set 10 ft
rock bridge at 240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed *H. Russell Bisher*
Well Plugging Supervisor

DATE 2-2-72
INV. NO. 5115-W