

CP3 R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

CHECKED OFFICE
FOR FILE NO.

FILE NO. _____
LOCATION SW NE SE
5/4-NE 1/4-NE 1/4
SEC. 33 TWP. 21 RGE. 16W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease WILE

Operator ROCKET DRILLING CO Address 204 DORBY BLDG WICHITA, KANS.

Field _____ County PAWNEE

Total Depth 3878 Feet.

Plugging Contractor R & D CASING PULLING CO

Plugging Contractor's License No. 236

Address Box 569 ELLIWOOD, KANSAS
(Describe Briefly the manner in which the well was plugged)

8 7/8 SURFACE PIPE 991' CWC - 380 SACKS - 5 1/4 - 3878'
TOP PERFORATION 3836' - SANDED TO 382.5' AND
5 SACKS CEMENT PLUG - FILLED HOLE W/MUD TO 990'
SET ROCK BRIDGE + 30 SX CMT PLUG - FILLED W/MUD
TO 300' - SET BRIDGE + 25 SX CMT - FILLED HOLE
W/MUD TO 30' - SET BRIDGE - CEMENTED TO BASE
OF CELLAR W/10 SX CEMENT CAP

Frank Brantley
District Conservation Agent

Date 12-26-57

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE: SEC 33 T 21 R 16W
BOOK PAGE 108 LINE 3