

15135-00551-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1964
7-29-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name R. W. Shields

Complete Address: 666 4th Natl Bk Bldg Wichita, Kans

Lease Name Elmore Well No. 2

Location NE SE NE Sec. 12 Twp. 18 Rge. (E) (W) 21

County Ness Total Depth 4189

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Halliburton Co

Address: Hays, Kansas License No.

Operation Completed: Hour 5PM Day 24 Month 7 Year 64

The Above well was plugged as follows:

8 5/8" 252' circulated with cement - 5 1/2" 4187' with 100 sax cement
and squeezed in Dakota 5 times - cement circulated - no pipe recovery.

Tried to drill hole out - lost hole at 1105' - circulated hole with heavy
mud - displaced 20 sax cement through 2" tubing at 550' - heavy mud to
240' - displaced 20 sax cement through 2" tubing at ~~20~~ 240' - heavy mud
to 40' - filled with cement 40' to 0'.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

DATE 9/29/64
INV. NO. 252-W

Signed: [Signature]
Well Plugging Supervisor