



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

15:135:06678:0000

CP3

State Corporation Commission

CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 5 1959
 11-5-59
 CONSERVATION DIVISION
 Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date Nov 1, 1959, authorized the following plugging operation:

Operator's Full Name: R. F. Shields
 Complete Address: Rule Bed Wichita Kansas
 Lease Name: Elmore Well No. B1
 Location: Twp. 18 Sec. 12 Twp. 18 Rge. 21 (E) (W)
 County: Wess Total Depth: 4210
 Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Gun pits circulate hole with heavy mud, set cementing plug at 600 ft. and displace 20 sac cement thru drill pipe, heavy mud to 270 ft set cementing plug, and displace 20 sac cement, heavy mud to 40 ft set and tie cementing in place with wire, dump $\frac{1}{2}$ sac hulls and displace 10 sac cement, cementing to base of cellar.

Very truly yours,
 Gilbert P. Leiker

Signed: Gilbert P. Leiker
 Conservation Division Agent