

15:135 60058 0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 14 1969
11-14-69
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name James W. Rockhold

Complete Address Box 698 Great Bend, Kansas 67530

Lease Name Elmore Well No. 1

Location NE NE NE Sec. 22 Twp. 18 Rge. (E) (W) 21

County Ness Total Depth 4625'

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 5P Day 12 Month 11 Year 1969

The above well was plugged as follows:

Total Depth 4625' 8 5/8 csg set at 268' cwc

5 1/2 csg set at 4238' cw 150 sk cmt.

5 1/2 csg pEBTD, 41140 With top perf. (4115) No pipe recovered

5 1/2 csg squeezed at 827' with 200 sk circ. to surface/

Pumped thru 5 1/2 plug container with 35 sk gel with 5 sk hulls, plug and 75 sk

50-50 poz cmt W/6% total gel. Max. pres. 1500 lbs. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben P. Dunsaul
Well Plugging Supervisor

DATE 11/14/69

INV. NO. 838-W