

KANSAS

Form CP-3
Rev. 6-4-68

15735-20605-0000

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 - 1972
5-1-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rains & Williamson Oil Co. & Thunderbird Drilling, Inc.
Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas
Lease Name Janke Well No. 1
Location NW SE NW Sec. 11R Twp. 18 Rge. (E) (W) 21R
County Ness Total Depth 4260'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 9 A Day 26 Month 4 Year 1972

The above well was plugged as follows:

RTD 4260' 8 5/8 csg set at 388' cwc: Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 330' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 5-3-72
INV. NO. 5670-10