

TYPE

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # Applied For \_\_\_\_\_ EXPIRATION DATE \_\_\_\_\_

OPERATOR R. J. Walker Oil Co., Inc. API NO. 15-115,20,906 0000

ADDRESS 3524 N. W. 56th Street COUNTY Marion

Oklahoma City, Oklahoma 73112 FIELD Wildcat-Undesignated *SCULLY*

\*\* CONTACT PERSON Oscar Goode PROD. FORMATION Viola

PHONE 405-949-2440

PURCHASER Koch Oil Company LEASE W. Scully

ADDRESS P. O. Box 2256 WELL NO. 6-10

Wichita, KS 67201 WELL LOCATION C SW SE SE

DRILLING CONTRACTOR Kansas Drilling & Well Serv., Inc. 330 Ft. from South Line and

ADDRESS Box 254 990 Ft. from East Line of

Marion, Kansas 66861 the (Qtr.) SEC 10 TWP 18 RGE 1E

PLUGGING N/A WELL PLAT \_\_\_\_\_ (Office Use Only)

CONTRACTOR ADDRESS \_\_\_\_\_

ADDRESS \_\_\_\_\_

\_\_\_\_\_

TOTAL DEPTH 3350' PBDT 3175'

SPUD DATE 7-14-82 DATE COMPLETED 7-23-82

ELEV: GR 1437' DF 1443' KB 1445

DRILLED WITH (~~CABLE~~) (ROTARY) (~~AIR~~) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE \_\_\_\_\_

Amount of surface pipe set and cemented 215' KB DV Tool Used? NO

THIS AFFIDAVIT APPLIES TO: (Circle ONE) Oil, Gas, Shut-in Gas, Dry, Disposal,

Injection, Temporarily Abandoned, OWWO. Other \_\_\_\_\_

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_


\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_



(Office Use Only)  
KCC   
KGS   
SWD/REP \_\_\_\_\_  
PLG. \_\_\_\_\_

A F F I D A V I T

O. N. Goode, Jr., being of lawful age, hereby certifies

that: I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct, to the best of my knowledge.

O. N. Goode, Jr.  
(Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 9th day of August, 1982.

Mary Kay Madrick  
(NOTARY PUBLIC)

MY COMMISSION EXPIRES: February 19th, 1985

RECEIVED

\*\* The person who can be reached by phone regarding any questions concerning this information.

AUG 10 1982

CONSERVATION DIVISION  
Wichita, Kansas

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR R. J. Walker Oil Co. Lease W. Scully #6-10 SEC. 10 TWP. 18 RGE. 1E

API #15-115-20,906

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
soil, shale, lime	0	225		
lime, shale	225	2112		
Lans	2112	2475		
K.C. Lans	2475	2647		
Fort Scott lime	2647	2653		
Cherokee Shale	2653	2711		
Miss Chat	2711	2795		
Miss lime	2795	2859		
Kinderhook	2859	3019		
Hunton	3019	3125		
Viola	3125	3235		
Simpson	3235	3295		
Arbuckle	3295	3350		
TD	3350			
"Driller's Log"				

RELEASED  
AUG 01 1982  
FROM CONFIDENTIAL

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (REPAIR)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	23	215' KB	Class A Common	150	Cmt Circ 3% CC
Production	7-7/8"	5 1/2"	17	3349' KB	Howcolite 50/50 Poz	200 125	2% Gel, 6% Salt 1% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
NONE			(Simpson) 4	.4 - jet	3238' to 40'
TUBING RECORD			Above perfs	isolated with	CIBP @ 3175'
Size 2-7/8"	Setting depth 3125'	Packer set at NONE	(Viola) 4	.4 - jet	3129' -31'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid-Simpson - 150 gal 15% mud acid - Howco - swb dry	3238'-3240'
Frac - Simpson 3000 gal gel 3% acid and 1000 gal gel form. wtr. 750# sd. Swb wtr.	3238'-3240'

Date of first production 8/7/82	Producing method (flowing, pumping, gas lift, etc.) swabbing	Gravity 35
------------------------------------	---	---------------

RATE OF PRODUCTION PER 24 HOURS	Oil 140	Gas TSTM	Water TR % 0	Gas-oil ratio TSTM	CFPB
---------------------------------	------------	-------------	-----------------	-----------------------	------

Disposition of gas (vented, used on lease or sold) vented	Perforations 3129'-31'
--	---------------------------

R. J. WALKER OIL CO., INC.  
150 FOUR CORPORATE PLAZA  
3524 NORTHWEST 56TH STREET  
OKLAHOMA CITY, OKLAHOMA 73112  
(405) 949-2440

January 20, 1984

State Corporation Commission of Kansas  
Conservation Division  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202

RE: CHANGE OF OPERATOR  
OLD OPERATOR - R. J. Walker Oil Co., Inc. #5606  
NEW OPERATOR - Panhandle Producing Company #9257  
601 N. W. Loop 410 - Suite 808  
San Antonio, Texas 78216

WELL: W. Scully #6-10; API #15-115-20,906; SW, SE, SE; Sec.  
10-T18S-R1E; Marion County, Kansas.

Gentlemen:

Please be advised the operator of the above well and lease is to be changed from R. J. Walker Oil Co., Inc. to Panhandle Producing Company, and that this change is effective as of November 1, 1983.

O. N. Goode

*O. N. Goode*

STATE OF OKLAHOMA )  
) SS.  
COUNTY OF OKLAHOMA )

O. N. Goode, of lawful age, being duly sworn upon oath, deposes and says that he is representative of R. J. Walker Oil Co., Inc. and that R. J. Walker Oil Co., Inc. has transferred operating ownership to Panhandle Producing Company in the W. Scully #6-10 well effective November 1, 1983, and that the above statements herein are true to the best of his knowledge and belief.

*O. N. Goode*

O. N. Goode

Subscribed and sworn to before me this 20th day of January, 1984.

My Commission Expires:

*Mary Kay Modrock*  
Notary Public

February 19, 1985

ONG/kw

cc: Panhandle Producing Company, San Antonio  
Charlie Miller

RECEIVED  
STATE CORPORATION COMMISSION

JAN 24 1984

CONSERVATION DIVISION  
Wichita, Kansas