

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
03/92
RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1994
1-11-94
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-135-20449-010 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Pickrell Drilling Company, Inc. KCC LICENSE # 5123 ^{6/94}
(owner/company name) (operator's)

ADDRESS 110 N. Market, Suite 205 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-8427

LEASE Dumler IM WELL# 1 SEC. 34 T. 16S R. 26 (~~East~~/West)

150' NE of C - SE - SE SPOT LOCATION/QQQQ COUNTY Ness

766 FEET (in exact footage) FROM (S) N (circle one) LINE OF SECTION (NOT Lease Line)

554 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 237 CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 4524 CEMENTED WITH 170 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: on bottom plus 340 sx thru DV tool @ 1994 ft.
O.H. 4524-4555, Perfs. 4421-4423 and 4405-4410

ELEVATION 2595 K.B. T.D. 4555 PBTD _____ ANHYDRITE DEPTH 1981 (+614)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Use 65/35 Poz plus 8% gel for cement. Mix and pump 200# of cottonseed hulls w/ first cement. Follow w/ cement until well pressures up (theoretical volume = 350 sx.) Have 50 sx extra on location, dig out cellar and check back side.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ed Mondero PHONE# (913) 798-2430

ADDRESS P.O. Box 375 City/State Ness City, Kansas 67560

PLUGGING CONTRACTOR Allied Cementing, Inc. KCC LICENSE # N/A
(company name) (contractor's)

ADDRESS P.O. Box 628, Great Bend, KS 67530-0628 PHONE # (816) 793-5861

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) January 13, 1994

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-7-94 AUTHORIZED OPERATOR/AGENT: Jack Gurley
(signature)