


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Crawford County, Sec. 28 Twp. 27S Rge. 22 (E) (W)  
Location as "NE/CNW&SW" or footage from lines SW SW SW SW  
Lease Owner E.J. Dunigan, Jr.  
Lease Name Nelson Well No. 1  
Office Address Box 261, Pampa Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 19 19 65  
Application for plugging filed June 19 19 65  
Application for plugging approved June 19 19 65  
Plugging commenced June 19 19 65  
Plugging completed June 19 19 65  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Victor Simonic & Buford Welch  
Producing formation None Depth to top Bottom Total Depth of Well 736' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
Soil & clay	None			7"	20'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran 5 sax on bottom  
Filled w/mud  
Set bridge @ 300'  
Ran 5 sax  
Filled w/mud  
Set bridge @ 25'  
Ran 5 sax & filled to surface

RECEIVED  
STATE CORPORATION COMMISSION

JUN 22 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K-K Drilling Company  
Address Chanute, Kansas

STATE OF Kansas, COUNTY OF Neosho, ss.  
James E. Guinotte (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James E. Guinotte  
Chanute, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 21st day of June, 19 65

My commission expires March 31, 1969 Notary Public.

WELL LOG - NELSON #1

GP

E. J. DUNIGAN, JR

28-27-22E

Contractor: K-K Drilling Co.

Location: SW SW SW SW  
Section 28-27S-22E  
Crawford County, Kansas

Comm: June 18, 1965  
Comp: June 19, 1965

Elevation - 1010'

Casing: 7" - 20'

THICKNESS  
OF STRATA

FORMATION

DEPTH

15	Soil & clay	15	
34	Shale	49	
5	Lime	54	
46	Shale	101	
10	Lime	111	
79	Shale	190	
38	Lime	228	Pawnee ls
34	Shale	262	
25	Shale & sdy sh	287	
19	Lime	306	Oswego ls
8	Shale	314	
11	Lime	325	
293	Shale	618	
6	Sand	624	) Tucker zone - wet
12	Shale	636	)
24	Sand	660	) Wet - no stain - no show
50	Shale	710	
10	Sand & coal	720	
16	Lime	736	Miss. lime

T.D. 736

Plugged

Bridge set @ 25 - ran 5 sax to surface  
Bridge set @ 300 - ran 5 sax  
5 sax on bottom

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 22 1965

CONSERVATION DIVISION  
Wichita, Kansas