

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1994

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

12-12-1994

LEASE OPERATOR William H. Davis

ADDRESS 2800 Mid-Continent Tower, Tulsa, OK 74103

PHONE#(918) 587-7782 OPERATORS LICENSE NO. 4511

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 7, 1994 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Stalnaker Depth to Top 3398 Bottom 3404 T.D. 4910

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Stalnaker</u>	<u>Gas</u>	<u>3384</u>	<u>3410</u>	<u>8-5/8</u> <u>4 1/2</u>	<u>290</u> <u>4025</u>	<u>0</u> <u>2700</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Allied Cementing pumped 5 sx sand, 5 sx cmt w/1 sx cottonseed hulls from PBTD of 3801' to 3200' 3100'. Cut off csg @ 2700'. Pmp 35 sx cmt plug @ 916', 35 sx plug @ 590', and 110 sx from 343' to surface. Let settle and topped off with 20 sx. Recovered 2700' 4 1/2" csg.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Operator License No. _____

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: William H. Davis

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Oran L. Hall

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Oran L. Hall

(Address) 2800 Mid-Continent Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 9th day of December, 1994

Wickie J. Foster
Notary Public

My Commission Expires: 7/6/97