

15.135-21218-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 34 Twp. 17S Rge. 23W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C SW NE

Lease Owner THEODORE I. LEBEN OIL OPERATIONS
Lease Name Howard Well No. 1
Office Address 1555 East Second, Wichita, Ks. 67214
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed 7-13 19 76
Application for plugging filed 7-13 19 76
Application for plugging approved 7-13 19 76
Plugging commenced 7-13 19 76
Plugging completed 7-13 19 76

Reason for abandonment of well or producing formation
No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4446
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Surf	287	8-5/8"	279	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Fluid to 600', plug, 70 sx cement;
Fluid to 240', plug, 20 sx cement;
Fluid to 40', plug, 10 sx cement.

RECEIVED
JUL 16 1976
7-16-76
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
701 First National Building
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 76

Ella Priess
Ella Priess Notary Public.

My commission expires 8-25-76

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976

DRILLERS' LOG

15 135-21218-0000

THEODORE I. LEBEN OIL OPERATIONS

No. 1 Howard
C SW NE, Sec. 34-17S-23W
Ness County, Kansas

Elev: 2388 K.B.

Commenced: 7-6-76
Complete: 7-13-76

Surface Casing: 279' of 8-5/8"
cemented w/175 sx common cement,
28 Gel, 38 cc. 7-7-76

FORMATION

DEPTH

Surface Hole	0 - 287
Shale, Iron Pyrite and Sand	287 - 883
Shale	883 - 1007
Blaine Anhydrite	1007 - 1016
Shale, Sand, Red Bed	1016 - 1658
Anhydrite	1658 - 1696
Shale	1696 - 2325
Shale & Lime	2325 - 2775
Lime	2775 - 2990
Lime & Shale	2990 - 3495
Lime, Shale & Sand	3495 - 3790
Lime	3790 - 4446 RTD

I do hereby certify that the foregoing statements are true and correct
to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 15th day of July, 1976.

Ella Priess
Ella Priess, Notary Public

10 1976
KANSAS
Sedgwick County, Kansas

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976