


15-007-00499-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Barber County, Sec. 19 Twp. 32S Rge. (E) 14 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Pickrell Drilling Company  
Lease Name Stumph-Fritz Well No. 1  
Office Address 705 Fourth Nat'l Bank Bldg. Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-7 1959  
Application for plugging filed 2-7 1959  
Application for plugging approved 2-7 1959  
Plugging commenced 2-7 1959  
Plugging completed 2-7 1959  
Reason for abandonment of well or producing formation Dry & Abandoned

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. LaKamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5033 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 190', bridge hole and cement with 30 sacks cement. Then heavy mud to 30' below ground level, bridge hole and cement with 10 sacks cement to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth Nat'l. Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. W. SEBITS

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. W. Sebits*  
705 Fourth Nat'l Bank Bldg., Wichita, Kansas  
(Address)

Subscribed and Sworn to before me this 11th day of February, 1959

My commission expires May 13, 1962

*Mary Ellen Sampson*  
(Mary Ellen Sampson) Notary Public.

PLUGGING  
FILE SEC 19 T 32 R 14W  
BOOK PAGE 16 LINE 39

15-007-00499-0000

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 1/19/59

Rotary Drilling Completed 2/7/59

LOCATION: NE NE NE, Sec. 19-32S-14W,  
Barber County, Kansas

CONTRACTOR: Stumph-Fritz #1  
PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: 200' (5 jts.) 13 3/8" 35.6# Armco Spiralweld Casing cemented with  
160 sacks cement, 2% Gel. Cement circulated.

D&A, No oil string run

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing:)

Sand	85'	Circ. for samples	4763'
Red Rock	200'		4961'
Pyrite	220'		4998'
Shale	520'		5033'
Shale & Shells	1440'		
Shale	1606'		
Lime	1645'		
Lime & Shale	1910'		
Lime	2130'		
Lime & Shale	2270'		
Lime	3025'		
Lime & Shale	3373'		
Lime	3670'		
Lime & Shale	4008'		
Lime	4763'		
Mississippi	4799'		
Lime	5033' T.D.		

S.L.M. at 2500 - OK  
3500 - OK  
4500 - OK

Slope Test at 2500 0° off  
3500 0° off  
4500 0° off

RECEIVED  
STATE CORPORATION DIVISION  
FEB 12 1959  
2-12-59  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 19 T 32 R 14W  
BOOK PAGE 16 LINE 39

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By C. W. Sebitts  
Attorney-in-Fact

STATE OF KANSAS, }  
COUNTY OF SEDGWICK } ss.:

On this 10th day of February, 1959, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 13, 1962

Mary Ellen Sampson  
Notary Public  
(Mary Ellen Sampson)