

15-007-00972-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 16 Twp. 32 Rge. (E) 14 (W)  
Location as "NE/CNWxSWx" or footage from lines SW NW NE  
Lease Owner Aylward Drilling Company  
Lease Name Barkley Well No. 3  
Office Address 909 First National Bank Building, Wichita, KS 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Gas Well  
Date well completed January 11, 19 82  
Application for plugging filed April 16, 19 82  
Application for plugging approved April 7, (verbally) 19 82  
Plugging commenced April 12, 19 82  
Plugging completed April 16, 19 82  
Reason for abandonment of well or producing formation Depletion



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production November 19 80  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation Douglas Sand Depth to top 3979 Bottom 3990 Total Depth of Well 4560 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	864	8 5/8"	864	None
		0	4559	5 1/2"	4559	3350'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mixed and pumped 12 sacks of gel, 6 sacks of cottonseed hulls, 13 sacks of gel and 150 sacks of common cement w/ 3% Calcium Chloride and 2% gel pumped down to 880 feet with finishing pressure holding at 400# psi.


RECEIVED  
STATE CORPORATION COMMISSION

APR 20 1982  
4-20-82

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling - Allied Cement Co.  
Address Box 176 Chase, Kansas 67524

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
P. Frank Hamlin, Manager (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. Frank Hamlin



SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 82

(Address) Norma Stoddard

My commission expires April 1, 1983

Notary Public.

BARKLEY #3

<u>Casing Record:</u>	<u>Company:</u>	Bachus Oil Co. & Aylward Drlg. Co.	<u>Location:</u>	SW NW NE Sec. 16-32S-14W Barber County Kansas
8 5/8 at 864 w/ 355 sacks cement	<u>Contractor:</u>	Bachus Oil Co.	<u>Elevation:</u>	1782 KB
5 1/2 at 4559 w/125 sacks cement	<u>Commenced:</u>	Nov. 1, 1962	<u>Production:</u>	2,743 MCF
	<u>Completed:</u>	Jan. 11, 1963	<u>Perforations:</u>	3979-3989

Formation:

From	To	
0	226	Red Bed Shale and Shells
226	375	Red Bed and Shells
375	735	Red Bed and shale
735	1084	Shale and Shells (Lost Circ. at 700')
1084	1170	Shale and Lime
1170	1420	Shale and Shells
1420	1680	Shale
1680	1955	Shale and Lime
1955	2837	Lime
2837	3120	Lime and Shale
3120	3210	Lime
3210	3435	Lime and Chalk
3435	3759	Lime and Shale
3759	3808	Shale and Sand
3808	3963	Shale Sand and Lime
3963	3978	Shale and Sand
3978	3990	Sand
3990	3996	Shale and Sand
3996	4112	Lime
4112	4233	Lime and Chalk
4233	4286	Lime
4286	4387	Lime and Chalk
4387	4421	Lime
4421	4465	Lime and Chalk
4465	4483	Lime
4483	4514	Miss. Chert
4514	4560	Chert and Lime
	4560	Total Depth

Electric Log Tops:

Heebner	3833
Douglas	3859
Lower Doug. Sand	3880-90
Lansing	3998
BKC	4400
Mississippian	4482
Total Depth	4560

RECEIVED  
STATE CORPORATION COMMISSION

1-26-82  
DST #1  
CONSERVATION DIVISION  
Wichita, Kansas

DST #1	3758-3808
	Open 1 hour, Rec. 1718' SW FP 232-891, BHP 1540-1518
DST #2	3858-3900
	Open 1 hour, Rec. 20' Mud FP 42-52, BHP 84-73
DST #3	3978-3990
	Open 48 Min., Rec. 2' Filtrate water and 1' distillate GTS 1 1/2 min. Ga. 6,650 MCF FP 1173-1194, BHP 1497-1497
DST #4	4483-4493
	Open 2 hours, plugging action first hour, Rec. 76' GCM GTS 7 Min., Ga 887 MCF IN 2 hours FP 135-198, BHP 1736-1683
DST #5	4493-4503
	Open 2 hours, Rec. 62' G&SO CM GTS 2 Min., Ga 556 MCF FP 130-130, BHP 1688-1593
DST #6	4503-4514
	Open 1 hour, Rec. 90' O&GCM and 180' SO&GCSW FP 52-120, BHP 1602-1326

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Nelson R. Thomas  
Nelson R. Thomas

Subscribed and sworn to before me this 16th day of January, 1963.

My commission expires October 14, 1964.

Lovene C. Ehrsam  
Lovene C. Ehrsam Notary Public