

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
111 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 15 Twp. 32S Rge. 14W (E) (W) XX

Location as "NE/CNWxSWx" or footage from lines SE SE NE  
Lease Owner Bowers Drilling Company, Inc.  
Lease Name Elsea "A" Well No. 1  
Office Address 1434 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-1 19 66  
Application for plugging filed 5-5 19 66  
Application for plugging approved 5-1 19 66  
Plugging commenced 5-1 19 66  
Plugging completed 5-1 19 66  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally



Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4474 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	888	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to 300'  
Set first plug at 300' with  
25 sacks cement  
Filled with heavy mud to 40'  
Set second plug at 40' with 10 sacks  
cement, 2 sacks in rathole

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 - 1966  
5-6-66  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bowers Drilling Company, Inc.  
Address 1434 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Emil E. Bowers (~~employee of owner~~) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers  
1434 Wichita Plaza  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of May, 1966  
Barbara J. Scott  
Notary Public.

My commission expires December 1, 1968



WELL LOG

COMPANY: Bowers Drilling Company, Inc.  
 CONTRACTOR: Bowers Drilling Company, Inc.  
 FARM: Elsea "A" #1  
 LOCATION: SE SE NE Section 15-32S-14W  
 Barber County, Kansas  
 COMMENCED: April 19, 1966  
 COMPLETED: May 1, 1966  
 ELEVATION: 1735 Kelly Bushing

0 - 889	Redbed and Shale	Set 8 5/8" casing at 888 with 175 sacks.
889 - 970	Shale	
970 - 1785	Shale and Shells	
1785 - 1975	Lime and Shale	
1975 - 2178	Shale and Shells	
2178 - 2960	Shale and Lime	
2960 - 3775	Lime	
3775 - 3910	Lime and Shale	
3910 - 4474	Lime	
4474	T. D.	

**ELECTRIC LOG TOPS:**

Elgin Zone	3558 (-1823)
Heebner	3764 (-2029)
Toronto	3780 (-2045)
Douglas Shale	3794 (-2059)
Lower Douglas Sand Zone	3896 (-2161)
Douglas Sand (Porosity)	3922 (-2187)
Lansing	3934 (-2199)
B/Kansas City	4335 (-2600)
Marmaton	4346 (-2611)
Mississippian	4417 (-2683)

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAY 6 - 1966  
 CONSERVATION DIVISION  
 1015 West 10th Street

STATE OF KANSAS        )  
                                   ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Elsea "A" #1 located SE SE NE Section 15-32S-14W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company Inc.

Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 5th day of May, 1966.

Barbara J. Scott

My commission expires December 1, 1968.