


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Barber County, Sec. 14 Twp. 32 Rge. 14 (E) W. (W)  
Location as "NE/CNW/SW" or footage from lines C SW NW  
Lease Owner Bowers Drilling Co., Inc.  
Lease Name Elsea Well No. # 1  
Office Address 1434 Wichita Plaza ; Wichita, Kans. 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed December 19 71  
Application for plugging approved December 19 71  
Plugging commenced January 17 19 72  
Plugging completed January 31 19 72  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat


If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	919	None
				5 1/2"	4510	3475

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

January 17, 1972 Plugged off bottom. Dumped sand to 3850'. Mixed and dumped 5 sx of cement.  
January 31, 1972 Plugged off top. Set 10' rock bridge at 270'. Filled 8 5/8" surface casing from 270' to base of cellar with 3000 lb. P.S.I. ready-mix concrete.



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor RUSS CASING PULLING, INC.  
Address P. O. BOX 1082 ; GREAT BEND, KANSAS 67530

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers  
Suite 1425, 125 North Market (Address)

SUBSCRIBED AND SWORN to before me this 3rd day of March, 19 72

My commission expires May 12, 1973  
Carole A. Young Notary Public.



WELL LOG

<b>COMPANY:</b>	Bowers Drilling Company, Inc.
<b>CONTRACTOR:</b>	Bowers Drilling Company, Inc.
<b>FARE:</b>	Elsas #1
<b>LOCATION:</b>	C SW NW Section 14-32S-14W Barber County, Kansas
<b>COMMENCED:</b>	January 1, 1966
<b>COMPLETED:</b>	January 22, 1966
<b>ELEVATION:</b>	1722 Kelly Bushing

0 - 943	Redbed	Set 8-5/8" casing at 919 with 200 sacks
943 - 1565	Redbed and shells	
1565 - 2110	Shale and shells	
2110 - 2242	Lime	
2242 - 2310	Lime and shale	
2310 - 2613	Lime	
2613 - 4120	Lime and shale	
4120 - 4150	Lime	
4150 - 4175	Lime and shale	
4175 - 4276	Lime	
4276 - 4315	Lime and shale	
4315 - 4482	Lime	
4482 - 4515	Lime and chert	
4515 - 4588	Lime and shale	
4588 - 4622	Lime	
4622 - 4720	Lime and shale	
4720 - 4755	Lime	
4755 - 4777	Lime and chert	
4777 - 4833	Lime	
4833 - 4854	Lime and Simpson	Set 4 1/2" casing at 4510 with 160 sacks
4854 - 4885	Lime and sand	
4885	T. D.	

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 12 1972  
CONSERVATION DIVISION  
Wichita, Kansas

**LOG TOPS:**

Egin Zone	3536	Lansing	3916
Neober	3743	Base Kansas City	4322
Toronto	3758	Marston	4392
Douglas Shale	3774	Mississippian	4409
Lower Douglas Sand		Kinderhook Shale	4661
Eons	3874	Viola	4701
Lower Doug. (Porosity)	3887	Simpson	4821

STATE OF KANSAS            )  
                                  ) SS  
COUNTY OF SEDGWICK        )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Elsas #1 located C SW NW Section 14-32S-14W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 1st day of February, 1966.

*Donna F. Miller*  
Donna F. Miller, Notary Public

My commission expires May 1, 1966.