

TYPE

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # Applied For _____ EXPIRATION DATE _____
OPERATOR R. J. Walker Oil Company Inc. API NO. 15-115-20,904 0000
ADDRESS 3524 N. W. 56th Street COUNTY Marion
Oklahoma City, Oklahoma 73112 FIELD Wildcat-Undesignated SULLY
** CONTACT PERSON Oscar Goode PROD. FORMATION Viola
PHONE 405-949-2440
PURCHASER Clear Creek, Inc. LEASE C. Meisinger
ADDRESS 818 Century Plaza Bldg. WELL NO. 1-15
Wichita, KS 67202 WELL LOCATION C NE NE NW
DRILLING Kansas Drilling & Well Serv., Inc. 330 Ft. from North Line and
CONTRACTOR ADDRESS Box 254 330 Ft. from East Line of
Marion, Kansas 66861 the NW (Qtr.) SEC 15 TWP 18S RGE 1E.

PLUGGING N/A
CONTRACTOR _____
ADDRESS _____

WELL PLAT (Office Use Only)
KCC [checked]
KGS [checked]
SWD/REP _____
PLG. _____

TOTAL DEPTH 3350' PBTD 3230'
SPUD DATE 6-7-82 DATE COMPLETED 6-15-82
ELEV: GR 1469' DF 1475' KB 1477'
DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.
DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 218' KB DV Tool Used? No
THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other
ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

O. N. Goode, Jr., being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct, to the best of my knowledge.

[Signature] (Name)

SUBSCRIBED AND SWORN TO BEFORE ME this 4th day of August, 1982.

[Signature] (NOTARY PUBLIC)

MY COMMISSION EXPIRES: February 19, 1985

RECEIVED STATE CORPORATION COMMISSION AUG 05 1982 CONSERVATION DIVISION Wichita, Kansas

** The person who can be reached by phone regarding any questions concerning this information.

SIDE TWO

OPERATOR R.J. Walker Oil Co LEASE C. Meisinger

#1-15

ACO-1 WELL HISTORY

SEC. 15 TWP. 18 RGE. 1E

FILL IN WELL LOG AS REQUIRED:

API# 15-115-20,904

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
soil, shale, lime	0	161		
lime, shale	161	2142		
Lans. K.C.	2142	2742		
Miss	2742	2833		
Miss lime	2833	3015		
Kinderhook	3015	3030		
Hunton	3030	3160		
Viola	3160	3257		
Simpson	3257	3309		
Arbuckle	3309	3350		
TD	3350			

"Drillers Logs"

RELEASED
JUL 01 1982

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or ~~CONFIDENTIAL~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	23	218'	Class A Common	150	Cmt Circ 3% CACL
Production	7-7/8"	5 1/2"	14	3333'	Howco Xlite 50/50 Poz	175	2% Gel; 6% salt 1% CFR-2

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none			4	.4 jet	3154'-58'
			4	.4 jet	3297'-3303'
			This zone isolated with CIBP @ 3292'		
			4	.4 jet	3259'-64'
			This zone isolated with CIBP @ 3230'		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid - 300 gal. 15% HCL - Viola	3154'-58'
Squeeze - 100 sxs Class A X 1% HA-9 & 3/4% CFR-2 in two stages - Simpson	3269'-71' & 3248'-50'

Date of first production 7/19/82	Producing method (flowing, pumping, gas lift, etc.) swabbing	Gravity 33
RATE OF PRODUCTION PER 24 HOURS Oil 24 bbls.	Gas TSTM MCF	Water 89 % 186 bbls.
Disposition of gas (vented, used on lease or sold) vented	Perforations 3154'-58' (4 JSPF)	

R. J. WALKER OIL CO., INC.
150 FOUR CORPORATE PLAZA
3524 NORTHWEST 56TH STREET
OKLAHOMA CITY, OKLAHOMA 73112
(405) 949-2440

January 20, 1984

State Corporation Commission of Kansas
Conservation Division
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202


RE: CHANGE OF OPERATOR
OLD OPERATOR - R. J. Walker Oil Co., Inc. #5606
NEW OPERATOR - Panhandle Producing Company #9257
601 N. W. Loop 410 - Suite 808
San Antonio, Texas 78216

WELL: C. Meisinger #1-15; API #15-115-20,904; NE, NE, NW; Sec.
15-T18S-R1E; Marion County, Kansas.

Gentlemen:

Please be advised the operator of the above well and lease is to be changed from R. J. Walker Oil Co., Inc. to Panhandle Producing Company, and that this change is effective as of November 1, 1983.

O. N. Goode



STATE OF OKLAHOMA)
) SS.
COUNTY OF OKLAHOMA)

O. N. Goode, of lawful age, being duly sworn upon oath, deposes and says that he is representative of R. J. Walker Oil Co., Inc. and that R. J. Walker Oil Co., Inc. has transferred operating ownership to Panhandle Producing Company in the C. Meisinger #1-15 well effective November 1, 1983, and that the above statements herein are true to the best of his knowledge and belief.



O. N. Goode

Subscribed and sworn to before me this 20th day of January, 1984.

My Commission Expires:



Mary Kay Medruck
Notary Public

February 19, 1985

ONG/kw

cc: Panhandle Producing Company, San Antonio
Charlie Miller

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1984

CONSERVATION DIVISION
Wichita, Kansas