


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

NESS County. Sec. 24 Twp. 16S Rge. 26W (E) (W)
Location as "NE/CNW/SW" or footage from lines. C NE NE
Lease Owner PICKRELL DRILLING COMPANY
Lease Name McKinnis "B" Well No. #1
Office Address 705 Fourth Nat'l Bank Bldg. Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-7-74 19
Application for plugging filed 11-7-74 19
Application for plugging approved 11-7-74 19
Plugging commenced 11-7-74 19
Plugging completed 11-7-74 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 4525 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	211'	None
RECEIVED STATE CORPORATION COMMISSION 11-21-74 NOV 21 1974 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug 850'. 70 sacks cement
Middle Plug 215'. 20 sacks cement
Top Plug 40'. 10 sacks cement. Job completed @ 8:30 A.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address 705 Fourth Nat'l Bank Bldg. Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth Nat'l Bank Bldg. Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of November, 1974

My commission expires August 19, 1975

Helen L. Martin
Notary Public.

ROTARY DRILLING LOG

15135-20963-0000

COMPANY: PICKRELL DRILLING COMPANY
 705 FOURTH NAT'L BANK BLDG.
LOCATION: WICHITA, KANSAS 67202
 MCKINNIS "B"
 C NE NE Sec. 24-16-26W
 NESS COUNTY, KANSAS
CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

Rotary Drilling Commenced 10-28-74
Rotary Drilling Completed 11-7-74

CASING RECORD: (5 joints) 8 5/8 surface casing set at 211' and cemented with 150 sacks cement. Job completed 10-28-74 at 6:30 P.M.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

		C. F. S.
40	Top Soil & clay	4420'
125	Post Rock	4475'
213	Shale	4490'
780	Shale	4501'
1490	Shale	4505'
1555	Sand	4515'
1695	Sand	4520'
1930	Shale	4525'
1950	Shale	
1983	Anhy.	
2275	Shale	
2640	Shale	
2809	Lime & Shale	
2915	Shale	
3115	Shale & Lime Stringer	
3270	Lime	
3410	Shale	
3560	Shale & Lime	
3730	Shale & Lime	
3865	Lime & Shale	
3995	Lime & Shale	
4075	Lime	
4150	Lime	
4217	Lime	
4280	Lime	
4325	Lime	
4380	Lime	
4435	Lime & Shale	
4460	Lime & Shale	
4475	Lime, Shale & Chert.	
4505	Lime & Shale	
4525	Mississippi	

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 21 1974
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 19th day of November, 19 74, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 19, 1975

Helen L. Martin
 Notary Public