

API NUMBER 15-135-23,706-0000

LEASE NAME Schoepf

WELL NUMBER 5

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 23 TWP. 16S RGE. 26 W7777(W)

COUNTY Ness

Date Well Completed 11/13/92

Plugging Commenced 11/13/92

Plugging Completed 11/13/92

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Jason Oil Company

ADDRESS P. O. Box 701, Russell, KS 67665

PHONE# (913) -483-4204 OPERATORS LICENSE NO. 6622

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-13-92 (date)

by Steve Middleton - Dan Goodrow was on location while plugging (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	302'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4575'-2050' 50 sks cement @ 330'  
50 sks cement @ 2050' 10 sks cement @ 40'  
80 sks cement @ 1180' 15 sks in rathole  
40 sks cement @ 600' 10 sks in mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
Kyle B. Branum

(Address) Box 506, Russell, KS 67665-0506

SUBSCRIBED AND SWORN TO before me this 17th day of November NOV 18 1992

Glenda R. Tiffin  
 Glenda R. Tiffin, Notary Public

GLENDA R. TIFFIN  
 NOTARY PUBLIC  
 STATE OF KANSAS  
 My Comm. Expires: 2-6-96

15:35.23706.0000

EMPHASIS OIL OPERATIONS

P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Jason Oil Company  
P. O. Box 701  
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Schoepf WELL #5

LOCATION: NW NW SE  
Section 23-16S-26W  
Ness County, Kansas

ROTARY TOTAL DEPTH: 4575'

ELEVATION: 2628' K.B.

COMMENCED: 11/5/92

COMPLETED: 11/13/92

CASING: 8-5/8" @ 302' w/180 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Dakota Sand	732'	Base Kansas City	4238'
Cedar Hills	1496'	Marmaton	4271'
Anhydrite	2016'	Pawnee	4371'
Shale	2048'	Ft. Scott	4444'
Heebner	3888'	Mississippi	4568'
Toronto	3906'	R.T.D.	4575'
Lansing-Kansas City	3928'		


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
Kyle B. Branum

Subscribed and sworn to before me on November 17, 1992.

My commission expires: February 6, 1996.



  
Glenda R. Tiffin, Notary Public

RECEIVED  
STATE OF KANSAS  
NOV 18 1992  
Wichita