

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
File or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 22 Twp. 16S Rge. 24W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
NW NE SE

Lease Owner Beren Corporation
Lease Name Casper Well No. #1
Office Address 970 Fourth Financial Center, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole

Date Well completed August 9, 1980 19
Application for plugging filed August 9, 1980 19
Application for plugging approved August 9, 1980 19
Plugging commenced August 9, 1980 19
Plugging completed August 9, 1980 19

Reason for abandonment of well or producing formation dry hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4593'
Show depth and thickness of all water, oil and gas formations.

GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows:
70 sacks at 1220', 25 sacks at 300', hulls and
10 sacks at 40', 3 sacks in rathole, 2 sacks in
mousehole. Plugging completed at 8:15 p.m.,
August 9, 1980.

RECEIVED
STATE CORPORATION COMMISSION
9-4-80
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 1980.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-84



D R I L L E R S L O G

15-135-21839-0000

#1 Casper

CASING RECORD:
8 jts. new 20#
8-5/8" surface
casing

COMPANY: Beren Corporation
CONTRACTOR: Strata Drilling Company
COMMENCED: August 1, 1980
COMPLETED: August 9, 1980

DESCRIPTION: NW NE SE
Section 22-16S-24W
Ness County, Kansas

TOTAL ROTARY
DEPTH: 4593'

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, shale	0	330	Ran 315' new 20# 8-5/8" surface casing; set and cemented at 320' with 200 sacks 60-40 pozmix, 3% C.C. Cement circulated. Plug down at 8:00 p.m., August 1, 1980.
Shale, sand, shale	330	2046	
Anhydrite	2046	2083	
Shale	2083	2790	
Lime and shale	2790	4060	
Lime	4060	4230	Ran 5 drill stem tests.
Lime and shale	4230	4455	
Lime	4455	4586	Ran 1 electric log.
Mississippi	4586	4593	

Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks at 1220', 25 sacks at 300', hulls and 10 sacks at 40', 3 sacks in rathole, 2 sacks in mousehole. Plugging completed at 8:15 p.m., August 9, 1980.

RECEIVED
STATE OF KANSAS
CONSERVATION DIVISION

SEP 11 1980

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp

Sworn to and subscribed before me this 22nd day of August, 1980.

my appointment expires 3-28-84.

Loneita Barry
Loneita Barry, Notary Public

