

15.135.20614.0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County, Sec. 22 Twp. 16S Rge. ~~XE~~ 26 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW  
Lease Owner Pickrell Drilling Company  
Lease Name Peters "B" Well No. 1  
Office Address 705 Fourth National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 25 19 72  
Application for plugging filed May 25 19 72  
Application for plugging approved May 25 19 72  
Plugging commenced May 25 19 72  
Plugging completed May 25 19 72  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4590 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	259'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug @ 800' w/70 sacks, Middle Plug @ 240' w/20 sacks,  
Top Plug @ 40' w/10 sacks.


RECEIVED  
STATE CORPORATION COMMISSION  
JUN 8 1972  
6-8-72  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Pickrell Drilling Company  
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts  
705 Fourth National Bank Bldg, Wichita, Kansas  
(Address)



Subscribed and signed to before me this 6th day of June, 1972  
Esther Lamone  
Esther Lamone  
Notary Public.  
My commission expires January 19, 1973

ROTARY DRILLING LOG

15:135-20614-0000

COMPANY: Pickrell Drilling Company  
705 Fourth National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced 5/15/72

Rotary Drilling Completed 5/25/72

LOCATION: Peters "B" No. 1, C NW NW Sec. 22-16S-26W,  
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: Run 6 Jts. 8-5/8" surface casing set @ 259' K.B. Cemented with  
160 sacks. Completed 5:00 P.M. Circulated.

No oil string run. D & A, Plugged 8:15 May 25, 1972.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

50	Surface Soil	C.F.S.
70	Sand	<u>4490</u>
261	Shale & Shells	4560
1605	Shale	4575
1815	Sand	4585
1951	Shale	4590
2105	Anhydrite	
2470	Shale	
2690	Shale & Lime	
2930	Lime	
3180	Lime & Shale	
3315	Shale	
3435	Shale & Sandy Lime	
3565	Lime - Shale	
3665	Shale	
3820	Shale & Sandy Lime	Slope Tests
3950	Lime - Shale	<u>2000</u>
4010	Shale & Lime	2500
4100	Lime & Shale	3000
4228	Lime	3500
4290	Lime & Shale	4000
4504	Lime	4500
4555	Lime & Shale	
4575	Lime & Chert	
4590	Miss., RTD	

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 8 1972  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]  
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 6th day of June, 19 72, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My Commission expires: January 19, 1973

[Signature]  
Esther Lamone Notary Public

