


15-007 - 20840-00 00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 11 Twp. 32S Rge 10W R&K
Location as "NE/CNW/SW" or footage from lines
1980 1320' FSL and 660' FEL
Lease Owner Wells Energy Company
Lease Name Schreiner Well No. 1
Office Address 700 So. Colorado Blvd., Denver, Colo.
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole
Date Well completed December 9, 1979
Application for plugging filed Verbal Application 1979
Application for plugging approved Verbal Approval 1979
Plugging commenced December 9, 1979
Plugging completed December 9, 1979
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 1979

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4444'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	244'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4444' (rotary total depth) to 240 ft. Set plug at 240 ft. and cemented with 40 sacks cement.
Filled hole with heavy rotary mud from 240 ft. to 40 ft. Set solid plug at 40 ft. and cemented with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Dowell Div., Dow Chemical Co. cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell Div., Dow Chemical Co.
Hwy 281 & Santa Fe, Pratt, Kansas 67124

RECEIVED
DEC 17 1979
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick
Merle Britting, Agent ~~xxxxxxx~~ of owner ~~xxxxxxx~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting
200 No. Main, Wichita, Kansas 67202
(Address)



SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 79

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Wells Energy Company

SEC. 11 T. 32S R. 10W

FARM Schreiner NO. 1

LOC. 1320' FSL and 1980 660' FEL

COUNTY Barber

ROTARY TOTAL DEPTH 4444'
COMM. November 28, 1979 COMP. December 9, 1979
CONTRACTOR H-30, Inc. (Rig 5)
ISSUED December 14, 1979

CASING

10 3/4"
8 5/8" Set at 244' cemented w/250 sxs cement
5 1/2"
4 1/2"

ELEVATION 1503' G.L.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	10'
Red Bed Sand and Shale	1340'
Shale and Lime	1935'
Lime and Shale	2160'
Shale and Lime	2422'
Lime and Shale	2915'
Shale and Lime	3165'
Lime and Shale	3730'
Shale and Lime	3869'
Lime and Shale	4159'
Shale and Lime	4283'
Lime and Shale	4374'
Shale and Lime	4444'
Rotary Total Depth	4444'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Merle Britting
Merle Britting

State of Kansas)
County of Sedgwick) ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 14th. day of December, 1979.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

