


WELL PLUGGING RECORD

Information Completely
on Required Affidavit
Deliver Report to:
Conservation Division
State Corporation Commission
211 So. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 11 Twp 32S Rge. 10W (E) (W)
Location as NE/CNW/SW or feature from lines NW NW NW
Lease Owner Pickrell Drilling Company
Lease Name Slinker Well No. 1
Office Address 705 1/2 National Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed February 26, 1963 19____
Application for plugging approved February 27, 1963 19____
Plugging commenced March 1, 1963 19____
Plugging completed March 4, 1963 19____
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3360 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	160	none
				4 1/2	none	363 1/2

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved on and rigged up unit. Cleaned out casing, rigged up jacks and measured T.D. Finished rigging up and worked trying to knock bridge out. Shot @ 359 1/2' and worked pipe. Started pulling pipe. Pulled rest of pipe and plugged well. Built 18' rock bridge @ 200' and filled hole and rock bridge. Capped well with 10 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1963
03-12-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1963

Carolyn Leven Notary Public.

My commission expires July 23, 1966

ROTARY DRILLING LOG

15-007-00186-00-00

COMPANY: **Pickrell Drilling Company, etal**
Wichita, Kansas

Rotary Drilling Commenced 4/30/56

LOCATION: **Slinker #1 NW NW NW Sec. 11-32-10W**
Barber County, Kansas

Rotary Drilling Completed 5/16/56

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD:

160' of 8 5/8" Spiralweld casing cemented with 135 sacks cement circulated.

115 Jts 4 1/2" J-55 set with 85 sacks cement at 1060

LOG

(Figures indicate bottom of formation - measurements from top of rotary lashing.)

Red rock	160	circ. for samples at	3617
Shale & Red Rock	235		4340
Red rock	265		4350
Red Red Shale & shells	955		4365
Shale & Shells	1405		4380
Line	2355		4400
Line & shale	2545		4415
Shale	2645		4423
Line & shale	3617		4470
Line	4330		
Mississippi Line	4470 LTD		

Drops Test at 1000' - O.K.
 2500' - O.K.
 3500' - O.K.

L.L. at 1000' - 0° off
 S.L. at 2500' - 0° off
 S.L. at 3500' - 0° off

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 6 1963
 03-06-1963
 CONSERVATION DIVISION
 WICHITA, KANSAS

The undersigned, E. J. Dill, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

E. J. Dill
 Attorney-in-Fact

STATE OF KANSAS

COUNTY OF BARBER

On this 15th day of July, 1956, before me the undersigned, a Notary Public, in and for the State of Kansas, appeared E. J. Dill, known to me to be the person whose name is subscribed to the foregoing instrument as its Attorney-in-Fact, and he acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and lawful act and deed of the PICKRELL DRILLING COMPANY for the uses and purposes therein set forth.

Witness my hand and seal of office this 15th day of July, 1956.

Alvin C. Hester
 Notary Public

July 10, 1956