

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-30161-00-00

LEASE NAME Wenzel

WELL NUMBER #1

SPOT LOCATION C NE NW

SEC. 11 TWP. 32 SRGE. 10 (E) or (W)

COUNTY Barber

Date Well Completed 4-1-65

Plugging Commenced 3-11-86

Plugging Completed 3-17-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Edmiston Oil Co., Inc

ADDRESS 1260 KSB Bldg. Wichita, Kansas 67202

PHONE # (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4369'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	244'	none
				4-1/2"	4370'	3459'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4120' and 4 sacks cement. Shot casing @3459' and pulled a total of 106 joints (3459') of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 100 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1986



My Commission expires:

MAR 27 1986
03-27-1986
CONSERVATION DIVISION
Wichita, Kansas

15-007-30161-00-00

SCHLUMBERGER

LATEROLOG

WITH GAMMA RAY

SCHLUMBERGER WELL SURVEYING CORPORATION
Houston, Texas

COUNTY BARBER - KANSAS FIELD or LOCATION SEC. 11-32S-10W WELL WENZEL NO. 1 COMPANY E. K. EDMISTON	COMPANY	E. K. EDMISTON	Other Surveys SONIC/CALIPER
	WELL	WENZEL NO. 1	
	FIELD	SHARON NW	
	LOCATION	SEC. 11-32S-10W C NE NW	
	COUNTY	BARBER	DIVISION Elevation: K.B.: 1508 D.F.: ---- or G.L.: 1503
STATE	KANSAS		

Log Depths Measured From KB 5 Ft. above GL

RUN No.	ONE	<i>49,904 WLB</i>	
Date	4-1-65		
First Reading	4366		
Last Reading	247		
Feet Measured	4119		
Csg. Schlum.	247		
Csg. Driller	8 5/8 @ 240		
Depth Reached	4369		
Bottom Driller	4370		
Mud Nat.	SALT GEL		
Dens.	9.4	38	
Visc.			
Mud Resist.	.0771 @ 78 °F	@ °F	@ °F
Res. BHT	.057 @ 112 °F	@ °F	@ °F
pH	6.0 @ --- °F	@ °F	@ °F
Wtr. Loss	10.4 CC 30 min	CC 30 min	CC 30 min
Rml (M)	.038 @ 112 °F	.0526 @ 78 °F	@ °F
Rmc (C)	.16 @ 112 °F	@ °F	@ °F
Bit Size	7 7/8 "		
Laterolog 3	a= 6" ;L= 3'	a=	L=
Laterolog 7	a= ;L=	a=	L=
Opr. Rig Time	1 1/2 HOURS		
Truck No.	2946 - WICHITA		
Recorded By	JACOBS		
Witness	SPEER		

K. G. S. LIBRARY

RECEIVED
STATE # REGULATION COMMISSION
JAN 21 1966
CONSERVATION DIVISION

REMARKS: CALIBRATION: BACKGND. SOURCE GALV. INCR. SENS. TAP RECORDING TIME SPEED LET MIN