


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-007-01504-00-00

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

BARBER County. Sec. 11 Twp. 32S Rge. 10W (E) (W)
Location as "NE/CNWSW" or footage from lines G NW NE
Lease Owner E. H. Wood, Jr.
Lease Name ZVOLANEK Well No. 1
Office Address 810 Union Nat'l. Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed September 25, 19 64
Application for plugging filed September 25, 19 64
Application for plugging approved September 25, 19 64
Plugging commenced September 25, 19 64
Plugging completed September 25, 19 64
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Herman E. Justus, Nickerson, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Red Bed and Shale</u>	<u>Surface Casing</u>	<u>-0-</u>	<u>208'</u>	<u>8-5/8"</u>	<u>208'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED HOLE: Filled hole with mud to 200'.
Put in 1/2 sk. hulls, plug
& 25 sx. cement.
Filled with mud to 40'. Put
in 1/2 sk. hulls, plug & 10
sx. cement.
Job completed at 12 Midnight.

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1964
09-30-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 1015 Wichita Plaza Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
S. P. Hall, Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. S. P. Hall
(Signature) S. P. Hall, Superintendent
Box 232, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of September, 19 64

Henry Orey
Notary Public.

My commission expires 10-17-67

15-007-01504-00-00

E. H. WOOD, JR. - Operator

SIERRA PETROLEUM CO., INC. - Contractor

ZVOLANEK #1
C NW NE
Sec. 11-32S-10W
Barber County, Kansas

T. D.: 4410'
Elev.: 1507' K.B.

Commenced: 9-14-64
Completed: 9-25-64

Casing:
8-5/8" Set at 208'

Cement:
with 165 sx. Common GL-3

FORMATION

DEPTH

Red Bed & Shale	208
Red Bed	310
Red Bed, Shale & Shells	1200
Shale & Salt	1360
Shale & Shells	1480
Shale & Lime Streaks	1550
Lime & Shale	3590
Sand	3659
Lime & Shale	3760
Lime	4360
Lime & Chert	4397
Chert	4410

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1964
09-30-1964
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

B. R. Hall
Superintendent

Subscribed and sworn to before me this 29th day of September, 1964.

Lesay Ditz
Notary Public

My commission expires: 10-17-67