

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Barber County. Sec. 10 Twp. 32S Rge. 10W (#/)(W)
Location as "NE/CNW&SW¼" or footage from lines. C E/2 NE SE
Lease Owner National Cooperative Refinery Association
Lease Name DOHM Well No. 1
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed February 15, 19 57
Application for plugging filed June 30, 19 64
Application for plugging approved July 1, 19 64
Plugging commenced July 2, 19 64
Plugging completed July 5, 19 64
Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4445 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	None-Cemented
				5-1/2"	4444'	3740'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 4340 feet. Shot 5 1/2" pipe off at 3720 feet.

Pulled 3740 feet of 5 1/2" pipe. Set rock bridge at 230 feet.

Dumped 25 sacks of cement. Mudded hole to 30 feet. Set rock

bridge and dumped 10 sacks of cement on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1964

07-14-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears

(employee of owner) or (owner-or-operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)

305 Rule Building, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July 19 64

My commission expires November 26, 1964.

Nell McComb

Notary Public.

15-007-01589-00-00
GABBERT-JONES DRILLING COMPANY, INC.
WICHITA, KANSAS
DRILLER'S WELL LOG

DOHM #1
C E/2 NE SE SECTION 10-32-10
BARBER COUNTY, KANSAS
COMMENCED 1-16-57
COMPLETED 2-2-57

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1964
07-01-1964
CONSERVATION DIVISION
Wichita, Kansas

FROM	DEPTH	To	FORMATION	REMARKS
0		130	SAND & RED BED	
130		220	SHALE & SHELLS	RAN 219' OF 8-5/8" CASING CEMENTED W/175 SACKS CEMENT.
220		625	RED BED	
625		1420	SHALE & SHELLS	
1420		2170	LIME	
2170		3670	LIME & SHALE	
3670		4345	LIME	
4345		4359	LIME, CHERTY	
4359		4400	LIME	
4400		4452	CHERTY LIME	
4452		TD		RAN 4463' OF 5 1/2" CASING CEMENTED ONE FOOT OFF BOTTOM W/50 SACKS CEMENT.

I, H. F. JONES, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE DRILLER'S WELL
LOG FOR THE DOHM #1 WELL.

H F Jones
H. F. JONES

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID
COUNTY AND STATE, ON THIS 7 DAY OF February, 1957, PERSONALLY
APPEARED H F Jones TO ME PERSONALLY KNOWN TO BE THE IDENTICAL
PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME
THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND
PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL
THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES

11-19-58

Summit & Hall
NOTARY PUBLIC