

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-01.021-0001

LEASE NAME DOHM 'A'

WELL NUMBER 1

SPOT LOCATION W/2-E/2-SW/4

SEC. 10 TWP. 32 RGE. 10 (W)

COUNTY Barber

Date Well Completed 10/2/87

Plugging Commenced 3PM 10/3/87

Plugging Completed 4PM 10/3/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR KBW Oil & Gas Company

ADDRESS PO Box H, Bethany, Oklahoma 73008

PHONE # (405) 789-0178 OPERATORS LICENSE NO. 5993

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation NONE Depth to top _____ bottom _____ T.O. 4700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Viola 4659-65'	Brine Water	0	220	8 5/8ths	220	None, cem. w/175 sks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Mud 9.7#, 50 Vis., to 590'. Pumped 50 sks 60-40 pozmix, balance method @ 590'. Mud to 250', pumped 50 sks 60-40 pozmix, balanced method @ 250'. Push dry plug to 40', Pumped 10 sks cement. Plug down @ 4PM 10/3/87.
(No rathole or mousehole.)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Svc. W/ BJ-Titan Cem. Svcs. License No. 5429
Address PO Box 108 Attica, Ks. 67009

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Gordon W. Keen, President (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gordon W. Keen
(Address) PO Box H Bethany, Ok. 73008

SUBSCRIBED AND SWORN TO before me this 13th day of October, 1987

Richard D. Montgomery
STATE CORPORATION COMMISSION Notary Public

My Commission expires: 5-22-88

OCT 13 1987
10-13-1987
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4 1-84
Revised 06-83