

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
111 No. Broadway
Wichita, Kansas

Barber County, Sec. 10 Twp. 32S Rge. 10 (E) (W)

Location as "NE/CNW/SW" or footage from lines C W/2 E/2 SW/4

Lease Owner NCRA - Sunray Mid-Continent

Lease Name Dohm-Smith Unit Well No. 1

Office Address 305 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 16, 19 58

Application for plugging filed March 18, 19 58

Application for plugging approved March 19, 19 58

Plugging commenced March 16, 19 58


Plugging completed March 16, 19 58

Reason for abandonment of well or producing formation Well not capable of

Commercial Production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lac Kamp

Producing formation Depth to top Bottom Total Depth of Well 4450 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	220'	None-Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole to 195'. Set plug at 195' plus 15 sacks of cement. Mudded hole to 35', set Halliburton plug plus 10 sacks of cement to 4' below surface. Cementing by Halliburton Cementing Company. Job completed at 5:00 a.m. on March 16, 1958. Plugging Instructions by Mr. W. L. Lac Kamp.

(3 31 1958)

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones Drilling Company
Address Orpheum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of March, 1958

Nell McComb

Nell McComb Notary Public.

My commission expires November 26, 1960



DOHM - SMITH #1
0 3/4 E/2 S/4
Section 10-38-10N
DARKE COUNTY, INDIANA
Dr. Under 3-1-51
Completed 3-15-53

DEPTH		FOUNDTION	REMARKS
FOOT	FEET		
0	10	Gravel	Run 200.70' of 3-7/8" casing, cemented to 220' with 175 sacks cement, 3' C. C.
10	221	Red Sand	
221	1130	Red Sand - Shale	
1130	1130	Red Sand	
1130	1213	SHALE	
1213	1475	Shale & Lime	
1475	1715	Lime	
1715	1845	Sandy Lime	
1845	2090	Lime	
2090	2420	Shale & Sand	
2420	2510	Shale	
2510	2640	Shale & Lime	
2640	2845	Sandy Shale	
2845	3375	Lime & Shale	
3375	3920	Lime	
3920	3985	Lime & Shale	
3985	4255	Lime	
4255	4315	Shale & Lime	
4315	4375	Lime	
4375	4395	Lime & Shale	
4395	4415	Lime	
4415	4450	Shale & Lime	
4450	17		Day & abandoned

I, E. E. Hall, certify this to be a true and correct copy of the Driller's Well Log for the Dohm - Smith #1.

E. E. Hall
E. E. Hall

STATE OF INDIANA)
COUNTY OF SEDGWICK)
Do:

03-31-1953

Before me, the undersigned, a Notary Public, within and for said County and State, on this 12th day of March, 1953 personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

In witness whereof, I have hereunto set my hand and official seal the day and year last above written.

Sue D. Arnold
Sue D. Arnold - Notary Public

My commission expires November 9, 1959.

PLUGGING
101 328.104
891143