

LEASE NAME Ricke B

WELL NUMBER #1 Twin

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 7 TWP. 32 RGE. 10W (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 5-5-97

Plugging Completed 5-6-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Hummon Corporation

ADDRESS 950 N. Tyler Rd. Wichita, KS 67212-3240

PHONE# (316) 773-2300 OPERATORS LICENSE NO. 5050

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	250'	none
				5 1/2	4573'	2415'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s' Sanded bottom to 3514' and ran 5 sks cement. Shot well at 2585', worked pipe. Shot at 2415', worked pipe free. Pulled pipe to 600'. Load hole w/7 bbls fresh water. Mix 3 sks gel. Mix 50 sks cement & displaced to 345' w/8 bbls fresh water. Pull pipe to 280', load hole w/3 bbls water, mix 50 sks cement. Displaced to 57'. Pulled out rest of pipe. Circulated 20 sks cement from 40' to surface. Plugging complete. 60/40 poz 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524 05-21-1997

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hummon Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 97

[Signature]
 Notary Public

My Commission Expires:

