


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 7 Twp. 32 Rge. 10 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NE NW
Lease Owner Trans Era Petroleum, Inc.
Lease Name McKeever Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 2/13/53 19
Application for plugging filed 2/11/53 19
Application for plugging approved 2/11/53 19
Plugging commenced 2/12/53 19
Plugging completed 2/12/53 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4920 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	278	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Finished laying down drill pipe. Filled hole with heavy mud to 270', set wooden plug, 1/2 sack of hulls and 30 sacks of cement mixed and run through drill pipe.
Filled hole with mud to 30', set plug with 1/2 sack of hulls and 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Herbert R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Herbert R. Michaelis*
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of February, 1953

[Signature]
Notary Public.

My commission expires 2-8-54.

02-23-1953

PLUGGING
FILE SEC 7 T 32 R 1024
BOOK PAGE 29 INF 16

15-007-00444-00-00

Trans Era Petroleum, Inc.
McKeever #1

NW NE NW 7-32-10W
Barber County, Ks.

Total Depth: 4920'
Comm. 1/1/53
Comp. 2/13/53

Casing

10 3/4" Set @ 278'

Cement

225 sacks of Lehigh &
Monarch

Formation

Depth

Red Bed	280
Shale-sand-clay	880
Shale-broken shells-anhydrite	1090
Shale-salt	1215
Shale-shells	1490
Shale-anhydrite	1655
Lime-shale	3625
Lime-sand-shale	3675
Lime-shale	3778
Lime	3825
Lime-shale	3898
Lime	3917
Lime-shale	3950
Lime	4204
Lime-shale	4385
Lime	4445
Chert-lime	4470
Lime	4511
Lime-shale	4537
Lime	4587
Lime-shale	4700
Lime	4746
Lime-sand	4759
Sand	4770
Lime-shale	4810
Lime	4830
Lime-shale	4846
Shale	4884
Lime	4920'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to
the best of my knowledge.

Caro Batz

Subscribed and sworn to before me this 19th day of February, 1953.

[Signature]

Notary Public

My commission expires: 2-8-54.

RECORDED
SERIALIZED
INDEXED
02-23-1953

PLUGGING
FILE SEC 7 T 32 R 1024
BOOK PAGE 79 LINE 16