

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 12 Twp. 32 Rge. 14 (E) (W) x

Location as "NE/CNW/SW" or footage from lines. NW SW SW

Lease Owner Sierra Oil Co.

Lease Name Lake Well No. #1

Office Address 211 N. Broadway, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_\_\_

Application for plugging filed 5-7-70 19\_\_\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_\_\_


Plugging commenced 6-13-70 19\_\_\_\_

Plugging completed 6-16-70 19\_\_\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4433' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4432'	3560.96'
				8 5/8"	858'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 4075'. Mixed and ran 5 sacks cement thru dump bailer.

Mudded hole to 510', set 10' rock bridge. Mixed and ran 25 sacks cement thru dump bailer. Mudded hole to 50', set 10' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 18 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor: Southwest Casing Pulling Co.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBE AND SWORN to before me this 17 day of June, 19 70



October 1972

Sidney D. Miller  
Notary Public.

SIERRA PETROLEUM CO., INC. - Operator

T. D.: 4433'  
Elev.: 1681' K.B.

LAKE #1  
NW SW SW  
Sec. 12-32S-14W  
Barber County, Kansas

Commenced: 5-1-64  
Completed: 5-11-64

Casing:

8-5/8" Set at 858'  
5-1/2" Set at 4432'

Cement:

with 475 sx.  
with 150 sx. Pozmix

FORMATION

DEPTH

Red Bed  
Red Bed, Shale & Shells  
Shale  
Shale & Shells  
Shale & Lime Streaks  
Lime & Shale  
Lime  
Lime & Chert  
Lime  
Lime & Chat  
Lime & Chert

700  
1011  
1250  
1640  
1953  
3880  
4190  
4235  
4365  
4398  
4433

TOPS:

Heebner  
Toronto  
Douglass Shale  
Lansing  
Marmaton  
Mississippi

3704  
3715  
3757  
3879  
4292  
4373

RECEIVED  
STATE CORPORATION COMMISSION  
5-8-70  
MAY 8 1970  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hall

Subscribed and sworn to before me this 14th day of May, 1964.

Gray Ditz  
Notary Public

My commission expires: 10-17-67