


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD



Barber County, Sec 12 Twp 32S Rge. 14 (E) W (W)  
Location as "NE/CNWSWK" or footage from lines Approx. 150' NE of NW-SW-NW  
Lease Owner Bowers Drilling Company  
Lease Name Lake Well No. A #1  
Office Address 1434 Wichita Plaza Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed 2-2- 19 68  
Application for plugging filed August 19 69  
Application for plugging approved August 19 69  
Plugging commenced October 13 19 69  
Plugging completed October 16 19 69  
Reason for abandonment of well or producing formation No longer producing

If a producing well is abandoned, date of last production August 19 69  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren  
Producing formation Le Compton Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3822 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	228	None
				4 1/2	3820	3267

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

October 13, 1969 Dumped sand to 3450'. Mixed and dumped 4 sx of cement.

October 16, 1969 Set 10' rock bridge from 225' to 215'. Filled 8 5/8" casing with 3000# test ready mix cement, from 215' to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor RUSS CASING PULLING, INC.  
Address P. O. Box 1082 Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers  
1434 Wichita Plaza  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of November, 19 69

My commission expires May 12, 1973  
Carole A. Young Notary Public.

WELL LOG

COMPANY:  
 CONTRACTOR:  
 FARM:  
 LOCATION:  
 COMMENCED:  
 COMPLETED:  
 ELEVATION:

BOWERS DRILLING COMPANY, INC.  
 BOWERS DRILLING COMPANY, INC.  
 Lake "A" #1  
 App 150' NE of NW SW NW, 12-32S-14W  
 Barber County, Kansas  
 1-25-68  
 2-2-68  
 1656 Kelly Bushing

0 - 1030	Red Bed	0-5/8" set at 228' W/150 sacks
1030 - 1568	Red Bed, Shale	
1568 - 1870	Lime & Shale	
1870 - 2025	Lime	
2025 - 2190	Shale & Lime	
2190 - 2419	Lime	
2419 - 3710	Lime & Shale	
3710 - 3822	Lime	4-1/2" set at 3820' W/125 sacks
3822 -	T.D.	

LOG TOPS

Lecompton	3463 (-1807)
Heebner	3675 (-2020)
Toronto	3691 (-2034)
Douglas Shale	3707 (-2051)
Douglas Sand Zone	3806 (-2150)
Douglas Sand (porosity)	Not reached by Log- Est 3820 (-2164)
LTD	3820

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 3 - 69  
 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas


STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, Emil E. Sowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lake "A" #1 located Approx. 150' NE of NW-SW-NW of Section 12-32S-14W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Sowers*

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas this 7th day of February, 1968.

*Elaine Reichenberger*  
 Elaine Reichenberger, Notary Public



My Commission expires November 16, 1971.