

API NUMBER 15-007-224740000

LEASE NAME Hoagland

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2

490 Ft. from S Section Line

1070 Ft. from E Section Line

SEC. 10 TWP. 32S RGE. 14 (E or W)

COUNTY Barber

Date Well Completed 7/8/95

Plugging Commenced 7/8/95

Plugging Completed 7/8/95

LEASE OPERATOR James B Read Operating, Inc

ADDRESS P.O. Box 638, Ardmore, Okla 73402

PHONE# (405) 226-0055 OPERATORS' LICENSE NO. 31297

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/7/95 (date)

by Steve Pfeifer, Pratt, Ks (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation none Depth to Top _____ Bottom T.D. 4740

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 STATE CORPORATION COMMISSION
 8-18-95
 AUG 18 1995

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing B	slt oil, gas, SW	4112	4138	20"	43	none
Drum	slt gas, SW	4292	4308	13 3/8	117	none
Miss Chert	slt gas, SW	4577	4628	8 5/8	1007	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
 Bottom plug at 1038': 50 sks 60/40 Pozmix, 6% gel, in & out surf, mud below plug
 Middle plug at 450': 50 sks 60/40 Pozmix, 6% gel, inside of 8 5/8 csg, mud between
 Top plug at 40': 10 sks 60/40 Pozmix, 6% gel, 15 sks rat hole, 10 sks mouse hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Eagle Drilling, Inc License No. 5380

Address 3500 N Rock Road, Bldg 800A, Wichita, Ks 67226

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: James B Read Operating, Inc

STATE OF Oklahoma COUNTY OF _____, ss.

James B Read (Signature) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) PO Box 638, Ardmore, Okla 73402

SUBSCRIBED AND SWORN TO before me this 15 day of Aug, 19 95

Steve J. Sengal
 Notary Public

My Commission Expires: April 26, 1999