


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 9 Twp. 32 Rge. 14 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE SW SW

Lease Owner AYLward Drilling Company
Lease Name Barkley #2 Well No. _____
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 5/17/78 19____
Plugging completed 5/22/78 19____
Reason for abandonment of well or producing formation
depleted. _____

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4887
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	227	none
				5 1/2"	4149	3653

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 4000' and ran 5 sacks cement. Shot pipe at 3638', pulled 113 joints. Squeezed
well with 15 sacks gel, 5 sacks hulls and 10 sacks gel. Released plug and displaced with
125 sacks 50/50 pozmix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1978
5-24-78

CONSERVATION DIVISION
WICHITA

(If additional description is necessary, use back of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of May, 1978

My commission expires



Margaret Melcher
Notary Public.

BARKLEY #2

Casing Records:

8 5/8 at 227
w/225 sacks cement
2 3/4 Ca Cl
5 1/2 at 4149
w/75 sacks cement

Company: Bachus Oil Co. &
Aylward Drig. Co.
Contractor: Bachus Oil Co.
Commenced: Sept. 18, 1962
Completed: Nov. 11, 1962

Location: NE SW SW
Sec. 9-323-14W
Barber County
Kansas

Elevation: 1880 KB

Production: 3,287 MCF

Perforations: 4052-4082

Formation:

From	To	Description
0	620	Red Bed & Shale
620	1077	Red Bed Shale & Shalls
1077	1515	Red Bed & Shale
1515	1765	Red Bed Shale & Lime
1765	2595	Lime
2595	3269	Lime & Shale
3269	3355	Lime
3355	3495	Lime & Shale
3495	3670	Lime & Shale with Chalk
1670	3762	Lime & Shale
1762	3865	Lime with Sand
1865	4080	Lime
4080	4095	Sand
4095	4229	Lime
4229	4375	Lime & Chalk
4375	4579	Lime
4579	4615	Chert
4615	4725	Lime
4725	4771	Lime & Shale
4771	4793	Lime
4793	4843	Lime & Shale
4843	4849	Lime
4849	4885	Viola Lime
4885	4885	Total Depth

Electric Log Tops:

Heebner	3921
Douglas	3951
Douglas Sand	4054
Douglas Sand	4077
Lansing	4092
BKC	4500
Mississippian	4606
Kinderhook	4802
Viola	4850
Total Depth	4887

DST #1 4050-4095

Open 70 Min.
GTS in 2 Min.
Ga. 6,050 MCF in 3 Min.
Ga. 7,000 MCF in 30 Min.
Ga. 7,000 MCF in 45 Min.
Rec. 25' oil and 2' Filtrate Water
FP 847-1355
BHP 1511/30 - 1502/30

DST #2 4600-4615

Open 70 Min.
Rec 25' Mud
FP 31-31
BHP 52/30 - 94/30

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1978
4-17-78
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Nelson R. Thomas
Nelson R. Thomas

Subscribed and sworn to before me this 4th day of December, 1962.

Lovene C. Ehrman
Lovene C. Ehrman Notary Public

My commission expires October 14, 1964.