


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec 7 Twp 32 Rge 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE SW SW
Lease Owner Spector Pipe and Supply Inc.
Lease Name Stump-Smith Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed 7-1-52 _____
Application for plugging filed Oct. 30, 1966 _____
Application for plugging approved Oct. 31, 1966 _____
Plugging commenced October 1, 1966 _____
Plugging completed October 31, 1966 _____
Reason for abandonment of well or producing formation failure to produce
profitably
If a producing well is abandoned, date of last production _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Simpson Sand Depth to top 4961 Bottom 4963 Total Depth of Well 4970 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	400 ft.	none
				7"OD	4963 ft.	3801.29

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand to 4950 feet and dumped 6 sacks of cement. Mudded hole to 300 feet, set Rock Bridge, and dumped 30 sacks of cement. Mudded hole to 40 feet, set Rock Bridge, and dumped 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1966
12-21-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lynch Casing Pulling Co. 457
Address R.F.D. 4, Great Bend, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

(Address) _____

SUBSCRIBED AND SWORN TO before me this 2nd day of November, 19 66

My commission expires Dec 1, 1968

Elcie Casdy
Notary Public.


KANSAS GEOLOGICAL SURVEY
 502 East Murdock, Wichita, Kansas

Company- NATIONAL COOPERATIVE REFINERY ASSN
 Farm- Stump-Smith No. 1

SEC. 7 T. 32 R. 11W
 NE SW SW

Total Depth. 4970
 Comm. 5-21-52 Comp. 7-1-52
 Shot or Treated.
 Contractor. R. C. Patton Co.
 Issued. 8-30-52

County Barber
 KANSAS



CASING:
 10 3/4" 100' cem w/300 sx
 7" 4963' cem w/200 sx

Elevation. 1947

Production. I.P. 509 bbls & no wtr

Figures indicate Bottom of Formations.

surface soil	10
sand	40
rod beds, shells	68
shale red	110
gyp fine	131
shale, shells	400
shale red, shells	860
shale red, anhydrite	930
shale, shells	1115
shale red	1205
shale, shells, salt	1410
shale, shells	1785
anhydrite, shale	1870
lime, shale	2125
anhydrite, shale	2180
lime, shale	2475
lime	2568
lime, shale	3440
lime	3510
lime, shale	3580
lime	3665
lime, shale	3867
lime	4000
lime, shale	4165
sand	4172
sand, lime	4205
lime	4445
lime, shale	4482
lime	4627
lime, shale	4641
lime	4713
lime, shale	4735
lime	4766
lime, shale	4814
lime	4830
lime, shale	4868
lime cherty (Viola)	4893
lime	4906
lime cherty	4970
Total Depth	
Tops: Scout.	
Douglas Sand	4161
Kansas City	4185
Mississippi lime	4696
Viola	4868
Simpson sand	4961

RECEIVED
 STATE CORPORATION COMMISSION

MAY 17 1966
 S-17-66
 CONSERVATION DIVISION
 Wichita, Kansas