


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barber County, Sec. 7 Twp. 32S Rge. 14 (E) (W)



Locate well correctly on above Section Plot

Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner National Cooperative Refinery Association
Lease Name Stumph-Smith Well No. 7
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 18, 1959
Application for plugging filed June 18, 1959
Application for plugging approved June 22, 1959
Plugging commenced July 16, 1959
Plugging completed July 25, 1959
Reason for abandonment of well or producing formation Production casing was set, but the well was not capable of producing.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4975 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	290'	None-Cemented
				5-1/2"	4973'	4418'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Recovered 4418' of 5-1/2" production casing. Mudded hole to 280', set a 10' rock bridge plus 10 sacks of cement. Mudded hole to 40', set a 10' rock bridge plus 10 sacks of cement on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 3 1959
8-3-59
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Wilson, Inc. (If additional description is necessary, use BACK of this sheet)
Address 317 North Buffalo, Stafford, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears (C. R. Sears)
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 1959

My commission expires November 26, 1960

Nell McComb Notary Public.

PLUGGING
FILE SEC. 7 T. 32 R. 14
BOOK PAGE 46 LINE 24

DRILLER'S LOG

COMPANY: NATIONAL COOPERATIVE REFINERY ASSOCIATION
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: STUMPH-SMITH #7
 LOCATION: SE NW NW SECTION 7-32S-14W
 BARBER COUNTY, KANSAS
 COMMENCED: 5-17-59
 COMPLETED: 6-3-59

0	70	Rock
70	125	Shale and Lime
125	292	Shale and Shells
292	830	Shale and Shells
830	860	Shale and Shells
860	890	Anhydrite
890	1860	Shale and Shells
1860	2275	Lime and Shale
2275	2540	Lime
2540	2850	Lime and Shale
2850	4045	Shale and Lime
4045	4184	Shale and Shells
4184	4886	Lime
4886	4931	Lime and Chert
4931	4950	Lime
4950	4960	Lime and Shale
4960	4965	Lime and Chert
4965	4973	Shale
	<u>4973</u>	<u>Rotary Total Depth</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 19 1959
 6-19-59
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" surface casing @ 292' with 200 sacks Sunset cement.

I, Theodore I. Leben, do hereby certify that the above and foregoing is a true and correct copy of the log of the Stumph-Smith #7, located SE NW NW of Section 7-32S-14W, Barber County, Kansas, as reflected by the files of Leben Drilling, Inc.

Theodore I. Leben
 Theodore I. Leben

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of June, 1959.

Juanita M. Green
 Juanita M. Green, Notary Public

My Commission Expires:
 April 23, 1963

PLUGGING
 FILE SEC. 7 T. 32 R. 14W
 BOOK PAGE 46 LINE 24