

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 3 Twp. 32 Rge. 14 ~~14~~ (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW SW SE
Lease Owner Mull Drilling Company
Lease Name Barkley "B" Well No. 1
Office Address 6405 E. Kellogg, Wichita, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Oct. 22, 1956 19
Application for plugging filed Oct. 22, 1956 19
Application for plugging approved Oct. 22, 1956 19
Plugging commenced Oct. 22, 1956 19
Plugging completed Oct. 22, 1956 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation None Depth to top Bottom Total Depth of Well 4685 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Douglas		3881		8-5/8	200'	None
Brown Lime		3891				
Lansing		3899				
Mississippi		4437				
Kinderhook		4610				
Viola		4660				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled Hole with Mud to 200'
Wood Plug 20 Sacks Cement & 1/4 Sack Hulls
Filled hole w/ mud to 35'
Surface Wood Plug 1/4 Sack Hulls & 10 Sacks Cement. Circulated into cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mull Drilling Company
Address Wichita, Kans.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Joseph B. Brungardt, Jr. (employee of owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph B. Brungardt, Jr.
6405 E. Kellogg, Wichita 18, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 1956

My commission expires January 28, 1957

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1956
10-31-56
CONSERVATION DIVISION
Wichita, Kansas
Notary Public.

PLUGGING
FILE SEC. 3 T. 32 R. 14W
BOOK PAGE 110 LINE 13

DRILLING RECORD

Barkley "B" Well No. 1
SW SW SE Sec. 3-32S-14W
Barber County, Kansas

Casing Record

200' of 8-5/8" OD Surface Pipe
cemented w/ 150 sacks.

Well Commenced 10/4/56
Drilling Commenced 10/4/56
Drilling Completed 10/22/56
Work Completed 10/23/56

No Oil String - Dry Hole

WELL LOG

Surface Soil & Sand	0 - 50
Red Bed	50 - 195
Red Rock & Shale	195 - 640
Shale	640 - 1400
Shale & Shells	1400 - 1495
Salt Shale & Shells	1495 - 1700
Shale & Shells	1700 - 1780
Lime & Shale	1780 - 1835
Lime	1835 - 1985
Shale & Lime	1985 - 2100
Lime	2100 - 2355
Lime & Shale	2355 - 3880
Lime	3880 - 3890
Lime & Shale	3890 - 3925
Lime	3925 - 4012
Lime & Shale	4012 - 4050
Lime	4050 - 4075
Lime	4075 - 4257
Lime & Shale	4257 - 4290
Lime	4290 - 4437
Lime & Chert	4437 - 4458
Miss Lime Cherty	4458 - 4467
Lime	4467 - 4485
Shale & Lime	4485 - 4548
Lime	4548 - 4570
Lime - Shale	4570 - 4620
Shale	4620 - 4660
Viola (Cherty)	4660 - 4675
Lime & Chert	4675 - 4685
	Total Depth

RECEIVED
OIL AND GAS COMMISSION

PLUGGING
 FILE SEC 3 T. 32 R. 14 W. 14
 BOOK PAGE 110 LINE 18

OCT 31 1956
10-31-56
OIL AND GAS COMMISSION
Topeka, Kansas